


|                      |  |
|----------------------|--|
| Gauge                | 16 A60, 14 A60   |
| Hinge Reinforcements | 7 gauge  |
| Closer Reinforcement | Standard   |
| Flush metal top cap  | Standard or seamless   |
| Thickness            | 1 3/4" standard;<br>Custom thickness available                                       |
| Edge Seam            | Visible (standard) or seamless   |
| Steel Stiffeners     | 22 gauge; 4" wide; welded at each end and to faces of door                           |
| Details              | Space between steel stiffeners filled with fiberglass insulation for sound deadening |

| Fire Rating             |                    |               |                   |            |
|-------------------------|--------------------|---------------|-------------------|------------|
| Door Type               | Max Width          | Max height    | Minimum Thickness | Max Rating |
| Single Swing            | 4'-0" (48")        | 10'-0" (120") | 1 11/16"          | 180 min.   |
| Standard Pair           | 8'-0" (96")        | 10'-0" (120") | 1 11/16"          | 180 min.   |
| Double Egress           | 8'-0" (96")        | 10'-0" (120") | 1 11/16"          | 180 min.   |
| Oversized Single & Pair | 5'-0" (60") leaves | 12'-0" (144") | 1 3/4" to 2" only | 90 min.    |


*\* Astragals are required on all pairs*




**Concept Frames, Inc.**  
 2015 Industrial Drive, Newton, NC 28658  
 PH: 888-234-9455 Fax: 800-631-9089  
[www.ConceptFrames.Com](http://www.ConceptFrames.Com)

Date: 1-3-2012

**Steel Stiffened Doors**



|                      |   |
|----------------------|---|
| Gauge                | 18 A60, 16 A60, 14 A60  |
| Hinge Reinforcements | 7 gauge   |
| Closer Reinforcement | Standard  |
| Flush metal top cap  | Standard or seamless  |
| Thickness            | 1 3/8", 1 3/4", 2"  |
| Width                | 3'-6" (42") max   |
| Height               | 8'-0" (96") max   |
| Edge Seam            | Visible (standard) or seamless  |
| Core                 | 1.0 lb/ft <sup>3</sup> density polystyrene core; resistant to moisture, rot, and mildew |
| Details              | Core permanently bonded to door skins by high strength pressure sensitive adhesive      |


| Fire Rating            |                     |
|------------------------|---------------------|
| Max Rating             | 90 minute           |
| Max Width              | 3'-0" (36")         |
| Max Height             | 7'-0" (84")         |
| Minimum Door Thickness | 1 3/4"              |
| Fire Rating Door Type  | Single opening only |



Concept Frames, Inc.  
 2015 Industrial Drive, Newton, NC 28658  
 PH: 888-234-9455 Fax: 800-631-9089  
[www.ConceptFrames.Com](http://www.ConceptFrames.Com)

Date: 4-30-2014

**Polystyrene Doors**



|                             |  |
|-----------------------------|--|
| <b>Gauge</b>                | 16 A60 only  |
| <b>Hinge Reinforcements</b> | 7 gauge  |
| <b>Closer Reinforcement</b> | Standard   |
| <b>Flush metal top cap</b>  | Standard or seamless   |
| <b>Thickness</b>            | 1 3/4" only  |
| <b>Width</b>                | 4'-0" (48") max per leaves   |
| <b>Height</b>               | 8'-0" (96") max  |
| <b>Edge Seam</b>            | Visible (standard) or seamless   |
| <b>Core</b>                 | Pyrophobic proprietary core design only  |
| <b>Details</b>              | Core permanently bonded to door skins by high strength pressure sensitive adhesive |

| <b>Fire Rating</b> |                  |                   |                  |                   |
|--------------------|------------------|-------------------|------------------|-------------------|
| <b>Door Type</b>   | <b>Max Width</b> | <b>Max Height</b> | <b>Thickness</b> | <b>Max Rating</b> |
| Single Swing       | 4'-0" (48")      | 8'-0" (96")       | 1 3/4"           | 180 min.          |
| Standard Pair*     | 8'-0" (96")      | 8'-0" (96")       | 1 3/4"           | 180 min.          |
| Double Egress**    | 8'-0" (96")      | 8'-0" (96")       | 1 3/4"           | 90 min.           |

\* Astragals are required on all pairs  
 \*\* Astragal and fire exit hardware required on all double egress pairs

**Evaluated to UBC 7-2 (1997),  
 UL 10C (1998) and NFPA 252**


**Vision lites of 100 square inches are  
 approved up to 90 minutes**




Concept Frames, Inc.  
 2015 Industrial Drive, Newton, NC 28658  
 PH: 888-234-9455 Fax: 800-631-9089  
[www.ConceptFrames.Com](http://www.ConceptFrames.Com)

Date: 1-3-2012

Temperature Rise Doors



|                      |  |
|----------------------|--|
| Gauge                | 12 A60 Galvanealed Skins   |
| Hinge Reinforcements | 7 gauge  |
| Closer Reinforcement | Standard   |
| Flush metal top cap  | Standard or seamless   |
| Thickness            | 1 3/4" standard;<br>Custom thickness available                                       |
| Edge Seam            | Visible (standard) or seamless   |
| Steel Stiffeners     | 22 gauge; 4" wide; welded at each end and to faces of door                           |
| Details              | Space between steel stiffeners filled with fiberglass insulation for sound deadening |




**Concept Frames, Inc.**  
 2015 Industrial Drive, Newton, NC 28658  
 PH: 888-234-9455 Fax: 800-631-9089  
[www.ConceptFrames.Com](http://www.ConceptFrames.Com)

Date: 1-27-2015 By: KX

12 Gauge Doors


- 16 gauge #304 or #316 stainless steel doors with #3/4 Finish
- Door widths up to 3'-7"; heights up to 10'-0"
- 1.0 lb/ft<sup>3</sup> density polystyrene core permanently bonded to door skins on non fire rated doors
- Fire rated doors available with polystyrene core
- Beveled edge with visible hemmed seam
- Our stainless steel doors are fabricated to your specifications, providing flexibility for design



Concept Frames, Inc.  
2015 Industrial Drive, Newton, NC 28658  
PH: 888-234-9455 Fax: 800-631-9089  
[www.ConceptFrames.Com](http://www.ConceptFrames.Com)

Date: 1-27-2015

Stainless Steel Doors



**Concept Frames lead lined doors and frames:**

- Are fabricated from 16 or 14 gauge
- All doors are steel stiffened ; lead sheet is centered in the door
- Can be fitted with various lead thicknesses
- Are available in door widths up to 4'-0"; heights up to 10'-0";  
Larger frame sizes available.

Our custom doors and frames are fabricated to your specifications, providing flexibility for design requirements. We manufacture lead lined doors and frames to meet your construction demands.

## Concept Frames, Inc.

2015 Industrial Drive, Newton, NC 28658  
PH: 888-234-9455 Fax: 800-631-9089  
[www.ConceptFrames.Com](http://www.ConceptFrames.Com)

Drawn By: KX

Date: 1-27-2015

Lead Lined Doors and Frames